



Rosevear Surveying & Consulting

May 12, 2026

Dawn Duranleau, AIA, CCM, LEED GA
PreConstruction Manager

EXHIBIT A

Re: *NCSD Tonopah High School Sports Complex Construction Staking - Tonopah, Nevada.*

Rosevear Surveying & Consulting is pleased to submit for your review this proposal to provide professional services for your project. Please review the services carefully and Rosevear Surveying & Consulting will make revisions that you feel are appropriate and adjust the fees accordingly.

Rosevear Surveying & Consulting (RSC) will provide surveying services as follows:

SCOPE OF WORK

RSC shall include in our Base ("Bid") Proposals the cost of providing all labor, material, equipment, supervision, services, taxes, insurances, license, fees, overhead, and profit, etc. necessary or incidentally required to complete the Work identified in this package. Items not clearly shown on the drawings or indicated in other contract documents but reasonably inferable from the contract documents or necessary to the integrity and proper functioning of RSC's work are to be included in the Base ("Bid") Proposal value.

Complete all **Surveying & Staking Work** in accordance with the plans and specifications in conformity with the contract, and other documents listed in the RFP and this Scope of Work Proposal Package.

Related Specifications

Division 00 – Procurement and Contracting Requirements

Division 01 – General Requirements

Section 32 – Site Improvements

1. Scope of Work – **Survey** – Provide all materials, labor, equipment, and supervision for a complete scope of work per plans and specifications. This scope of work shall include, but not be limited to:
 - a. Perform all required calculations to create staking plan for all layout work from provided CAD background files.
 - b. Verify horizontal and vertical control points for surveying purposes.
 - c. Provide all control survey work for the entire project including verification of all horizontal and vertical controls, and (3) control points for GPS.
 - d. Provide and maintain all onsite control points and benchmarks.
 - e. Verify existing tie-in grades match grading plans.
 - f. Verify existing offsite elevation matches CAD file provided by Civil Engineer. Notify Contractor of findings within the first two (2) weeks following Notice to Proceed (NTP).
 - g. Provide record as-built survey document for new site wet and dry utilities.

- h. At completion of project, provide Project Monument Survey, as required for NCSD.
- 2. Scope of Work – **Layout & Staking** – Provide all materials, labor, equipment, and supervision for a complete scope of work per plans and specifications. This scope of work shall include, but not be limited to:
 - a. Stake Contractor's staging and parking area corners.
 - b. Demolition and Rough Grade Staking
 - i. Set demolition limits and site improvement grading.
 - c. Utility Staking
 - i. Domestic water lines including RPPA's.
 - ii. Irrigation water mains and RPPA.
 - iii. Sanitary sewer system including mains, laterals, cleanouts, area drains, drain inlets, and manholes.
 - iv. Storm sewer system, including mains, laterals, manholes, drop inlets, cleanouts, and manholes.
 - 1. Including synthetic turf and running track drainage systems.
 - 2. Including sand pit storm drainage systems.
 - NCSD Tonopah High School Sports Complex
 - v. Electrical & Low Voltage ductbanks, vaults, pedestals, transformers and site lighting, including sports field lighting.
 - vi. Transformer.
 - vii. Natural gas piping from meter location.
 - viii. Any known existing or located underground systems or utilities not listed above, including but not limited to septic tanks, grease interceptors, etc.
 - d. Building Staking
 - i. Stake rough grade for building pads at corners and with 40' minimum grid layout as needed.
 - ii. Redheads and blue top building pad staking.
 - iii. Sawcuts for all curbs, gutters, and paving to be removed.
 - iv. Provide Certified Building Pad documentation.
 - v. Finished Floor monument and elevation certification.
 - vi. Stake all building grid lines.
 - vii. Vertical grid line transfer, to top of footings and on slab-on-grade.
 - e. Paving Staking
 - i. Provide redheads and bluetops at running track at 50' intervals.
 - ii. Stake finish grades for asphalt running track at 50' intervals.
 - iii. Final staking including curb and gutter, sidewalks and flatwork.
 - f. Site Staking
 - i. Stake rough grade staking for entire site at 100' intervals.
 - ii. Stake all site concrete including curbs, gutters, sidewalks, and equipment & utility pads.
 - iii. Stake grade breaks, angle points, and curb transitions.
 - iv. Stake site amenities, including:
 - 1. Running track.
 - 2. Synthetic Turf field
 - 3. Bleachers.
 - 4. Pressbox.
 - 5. Ticket booth.
 - 6. Scoreboard poles.
 - 7. Chain link fencing.
 - 8. Athletic equipment, including:
 - a. Goal posts
 - b. Pole vault
 - c. Discus / shot put rings & toeboards
 - d. Discus cage
 - e. Long jump board
 - f. Soccer goals
 - 9. Sports lighting.
 - 10. Flagpoles.
 - g. Include as-builts / record of survey monuments.

3. Scope of Work – **General Scope Requirements** – The following requirements shall apply to all Work under this Scope of Work package:

a. Provide Hourly Rate Breakdown.
b. Include multiple mobilizations as may be required per the Preliminary Construction Schedule and Phased Logistics Plan.

- a. \$155.00 Professional Land Surveyor.
\$105.0 Survey Technician.
Supporting field crew staff hourly rates:
\$195.00 one-man crew Party Chief or Professional Land Surveyor.
\$295.00 two-man crew Professional Land Surveyor and Chain Man.”
- b. \$2,450.00 per additional mobilization, to verify previous staking and control.

RCS have estimated this task will take a minimum of 15 days onsite.

RSC have assumed a ten-hour workday, which includes travel to and from the job site. Our intention is to work a minimum of six-hours on site for each trip. Trips where additional consecutive days are required, an eight-hour onsite day will be scheduled. Our assumption for additional work outside of scope or re-stake will be billed (T & M) against 3. a. specifications.”

2026 - Base Bid - NCSD Tonopah High School Sports Complex

Fee. \$36,750.00

Fees quoted, include Base (“Bid”) Proposals the cost of providing all labor, material, equipment, supervision, services, taxes, insurances, license, fees, overhead, and profit, etc. necessary or incidentally required to complete the Work identified in this package. Items not clearly shown on the drawings or indicated in other contract documents but reasonably inferable from the contract documents or necessary to the integrity and proper functioning of the RSC Work are included in the Base (“Bid”) Proposal value.

If you need additional information regarding this proposal, please feel free to call the undersigned at your earliest convenience.

Sincerely

Rosevear Surveying & Consulting



Robert (Buzz) Rosevear, PLS, WRS – NV, UT
Owner