



CORE Construction, Inc.
5330 Reno Corporate Dr
Reno, NV 89511

NCSD-THS Field Replacement

ANI dba Gale Building Products submits the following proposal for the scope items specifically identified below. Please review all qualifications and exclusions at the end of the proposal.



ANI dba Gale Building Products
910 Meredith Way
Sparks, NV 89431
Bid Date: 5.11.26

Plans: 4.20.26 (KNIT)

D-Tono

Addenda: 1, C1,C2 Noted

Thermal Insulation:

- R-38 FSK fiberglass insulation applied to underside of metal deck structure at concession in accordance with details
- R-19 minimum polyiso rigid insulation mechanically fastened to exterior CMU perimeter partitions at concessions building in accordance with energy compliance report
 - Include tape at all seams/fasteners as required
- Unfaced fiberglass insulation applied to interior partitions scheduled for insulation with "A" modifier per wall schedule, full depth of cavities
 - R-19 at 6" / R-11 at 3-5/8"

Qualifications:

- Perimeter floor area to be free of stored material and equipment to ensure safe / efficient movement
- Maximum (2) mobilizations figured

Exclusions:

- Any rigid insulation associated with site, roof, or foundation/underslabs
- MEP insulation
- Insulation at joint assemblies (head of wall, caulking joints, expansion joints etc..)

Base: \$31,916.00

Alternates:

- Supply & install z-furring with rigidi insulation at exterior walls per RFI response 26 (verify continuous calc)
16 OC ADD \$12,726.00 / 24 OC ADD \$9,853.00
- Utilize 2" rigid ilo R-19 minimum per RFI 26 response (energy compliance states R-19 CI)
(DEDUCT: \$4,132.00)

Fluid Applied Membrane Air Barriers (No Spec):

Materials:

- Fluid applied vapor permeable membrane, self-adhered membrane transition strips and/or liquid flashing, primer as required for full system

Areas: Interior side of CMU exterior walls to receive rigid insulation, outboard face of concrete to receive cladding as integral to building envelope

Installation: Fluid membrane to be spray or roller applied to substrate. Terminations at rough openings and between dissimilar materials will be performed according to the manufacturer's recommendations using primer and self-adhering membrane or liquid flashing. All joints for termination strips will be firmly rolled with a non-metallic roller to ensure adhesion

**Qualifications:**

- Air barrier systems to be installed after structural connections and prior to all façade supports
- All joints or gaps larger than 1/4" in the substrate or large gaps around penetrations will need to be sealed by others prior to the installation of the air barrier
- The products used to close the gaps must be compatible with the fluid applied air barrier membrane
- All masonry joints are to be struck flush by others and clean of mortar and debris
- Concrete curing agents to be resin based without oil, wax or pigments
- Assumes work to be done at temps in compliance with manufacturer's installation process
- Low temperature products are available on the market and can be used during cold weather - will be priced accordingly if required
- Air barrier will be installed by elevations

Exclusions:

- All weeps, termination bars, caulking, mortar nets, steel shelf angles, aluminum plates, access panels, metal coping, thru-wall metal flashing, termination bars and galvanized channel
- Rainscreens, drainage mats
- Graffiti or clear coatings at exposed concrete/CMU
- All waterproofing, particularly at below grade and horizontal roofing conditions (by others)
- Responsibility for compatibility issues with adjoining construction including waterproofing and building envelop sealants
- Protection of substrate prior to installation of air barrier
- Conditioning of space (tenting and heating) for cold weather installation if needed
- Exclude all caulking outside of the air barrier scope.
- Exclude repairs for damage to the air barrier caused by other trades installing their material
 - Follow up trades are responsible for maintaining the integrity of the air barrier membrane while performing their scope of work

Base: \$22,511.00

NOTES & CLARIFICATIONS

1. **Materials & tasks not noted above are excluded from this proposal.**
2. **GBP not responsible for protection of installed materials.**
3. **Proposal scope inclusions and exclusions to be included within contract**
4. **Bid bond not included within price**
5. **Bid good for 30 days**

NCSD - Tonopah High School Sports Complex

1 Ray Tennant Way, Tonopah, NV 89049, United States of America

Sent proposal: \$54,427

Submitted May 11, 2026 at 2:43 PM PDT

Gale Building Products

5375 South Procyon Street, SUITE 1001, Las Vegas, NV 89118, United States of America

Marcus Boundy | +1 775-331-5600 | (775) 741-6145 | marcus.boundy@truteam.com

Line Items

Description	Quantity	Unit Cost	Total Cost
Thermal Rigid Insulation			\$0
Thermal Batt Insulation			\$0
Acoustical Batt Insulation			\$0
Acoustical Sealants			\$0
Firestopping, if applicable			\$0
Additional Items:			
Fluid Applied Air Barroer			\$22,511
Rigid, Thermal & Acoustical Insulation			\$31,916
Base Bid			\$54,427

General Acknowledgments

Bid Docs - HS Sports Complex Plans	Yes
Bid Docs - Exist. ES Demo Plans	Yes

Bond Information

Payment & Performance	0.55	%
-----------------------	------	---

Additional Information

Notes Please see attached proposal for insulation & fluid applied membrane

Attachments

 NCSD-THS-Field-Replaceme... (302 KB)