

**SECTION 13 3423
FABRICATED STRUCTURES**

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Pre-engineered shop-fabricated modular buildings.
- B. Handicap ramps.

1.02 DESIGN REQUIREMENTS

- A. Installed Thermal Resistance of Wall System: R value of R-13.
- B. Installed Thermal Resistance of Roof System: R value of R-19.
- C. Installed Thermal Resistance of Floor System: R value of R-11.
- D. Design Loades:
 - 1. Roofs: 20 psf
 - 2. Floors: 50 psf
 - 3. Wind: 80 mph, Exposure C, 22.6 psf
 - 4. Seismic Zone: 4

1.03 SUBMITTALS

- A. See Section 01 3000 - Administrative Requirements, for submittal procedures.
- B. Shop Drawings: Indicate construction dimensions, materials, wall and roof systems, windows, doors and hardware, finish schedule, electrical systems, mechanical systems, plumbing systems, sprinkler systems, and hold down systems.

1.04 QUALITY ASSURANCE

- A. Design structural components, develop shop drawings, and perform shop and site work under direct supervision of a Professional Structural Engineer experienced in design of this Work and licensed in the State of Nevada.
 - 1. Conform to applicable code for submission of design calculations as required for acquiring permits.
 - 2. Cooperate with regulatory agency or authority and provide data as requested.
- B. Manufacturer Qualifications: Company specializing in manufacturing products specified in this section, with not less than three years of documented experience.

1.05 PRE-INSTALLATION MEETING

- A. Convene one week before starting work of this section.

1.06 WARRANTY

- A. See Section 01 7000 - Closeout Submittals, for additional warranty requirements.
- B. Correct defective Work within a five year period after Date of Substantial Completion.

PART 2 PRODUCTS

2.01 PRE-ENGINEERED BUILDING

- A. Chassis: I-beam, quad axel, detachable hitch.
- B. Floor: Wood joist, 5/8" T&G Plywood.
- C. Exterior Walls: 2x4 HF Stud Grade, 7/16" wood siding, 4" wood trim.
- D. Interior Walls: 2x4 HF Stud Grade.
- E. Roof: LPDM Roofing, HF stud grade rafters.
- F. Skirting: Manufacturer's standard.

2.02 COMPONENTS

- A. Windows: Horizontal slider, bronze, dual pane.

- B. Doors: As indicated on drawings.
- C. Finishes: As indicated on drawings.
- D. Security Bars: Manufacturer's standard, fixed, painted black.
- E. Mini Blinds: Manufacturer's standard, white.
- F. Grab Bars: 36" long and 48" long mounted 34" a.f.f.
- G. Toilet Accessories: Toilet Paper Holder, 24"x36" Mirror mounted 38" a.f.f., liquid soap dispenser.

2.03 HANDICAP RAMP

- A. Manufacturer's standard metal ramp and handrails.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that grading, mechanical and electrical utilities, and placed anchors are in correct position

3.02 STARTING EQUIPMENT AND SYSTEMS

- A. Provide manufacturer's field representative to prepare and start equipment.

END OF SECTION