

NCSD - Tonopah High School Sports Complex

1 Ray Tennant Way, Tonopah, NV 89049, United States of America

Sent proposal: \$425,394

Submitted May 12, 2026 at 12:48 PM PDT

John Jackson Masonry

5960 Bradshaw Road, Sacramento, CA 95829, United States of America

Ben Sneed | ben@johnjacksonmasonry.com



General Acknowledgments

Bid Docs - HS Sports Complex Plans	Yes
Bid Docs - Exist. ES Demo Plans	Yes

Bond Information

Payment & Performance	1.65	%
-----------------------	------	---

Additional Information

Notes	Please see attached Bid Proposal for the Tonopah High School Sports Complex.
-------	--

Attachments

 Tonopah High School Bid Pro... (334 KB)



5960 Bradshaw Rd.
Sacramento, CA 95829
(916) 381-8021 * Fax (916) 381-1202
CA License 255203 * NV Lic 12071
DIR #: 1000000334
johnjacksonmasonry.com

PROPOSAL

Contractor: CORE Construction

Attention: Dawn Duranleau

Email: dawnduranleau@coreconstruction.com

Phone: (702) 926-1812

Project: Tonopah High School Sports Complex

Location: Tonopah, NV

Architect: KNIT Studios

Date: 5/12/2026 **Time:** 1:00 PM

We propose to furnish the labor and materials listed below according to the plans and specifications exhibited to us, and subject to all terms and conditions herein, for the sum of:

Base Bid: \$ 425,394

Scope of Work: 04 05 03 Masonry Mortaring and Grouting
04 20 16 Reinforced Unit Masonry
- CMU Concessions Building

Addm Noted: No. 1-2

Alternates: None

Clarifications:

- Masonry reinforcing is included
- Masonry scaffolding is included for John Jackson Masonry use only
- Proper access must be provided for scaffolding & forklift loading of material
- One mobilization is included-add \$4,000 for each additional mobilization
- **CMU is 2,000 psi; Medium Weight; Natural Gray Color; Precision Texture; IWR**

Exclusions:

Caulking, Sealants & Backer Rod
Sandblasting
Grouting post-installed hollow metal frames
Temporary bracing of CMU walls
Setting and bracing hollow metal frames
Costs of Bonds
Drypacking & Grouting Beam Pockets
Sealers, Waterproofing and Dampproofing
Veneer Backing (sheathing, building paper, etc.)
Footings
Furnishing, Locating & Installation of embeds, bolts, anchors, ties, flashing and miscellaneous metal items

Furnishing & Placing of Precast Items
Tie off during scaffold erection & dismantling
Wall Lines, Elevations and Dowel Layout
Demolition, Drilling, Welding & Doweling
Non-shrink Grout and Drypacking
Testing & Inspection
Lath and Plastering
Furnishing of Temporary Water & Power
Foundation Surface Preparation
Anti-graffiti Coatings

Payment schedule: Monthly progress billings, invoiced for work completed through the end of the month payable in full by the 10th of the following month. Retention percentage withheld by prime contractor shall not exceed that held by owner. All rights and privileges contained in the contract relating to retention and/or substitution of securities therefore shall accrue to subcontractor.

Proposal Expiration: This Quotation is valid for 10 days from above Bid Date.

Accepted:

JOHN JACKSON MASONRY

Benjamin Sneed
Ben Sneed-Cell#(530)902-1985

When accepted this proposal becomes a part of the Subcontract Agreement