

05/29/2026

CG&B Enterprises, Inc.
2250 Corporate Circle, Suite 320
Henderson, NV 89074
Office: 702-565-6564
Fax: 702-565-6727
Unlimited, NV A-General License (#39691)
Jeff Wasson, Lead Estimator
725-377-1979, j.wasson@cgandbinc.com

To: CORE Construction
Address: 7150 Cascade Valley Court
 Las Vegas, NV 89128

Attn: Chris Laux
Phone: (702) 985-2078
Email: chrislaux@coreconstruction.com

Project: Tonopah High School – Synthetic Turf System Supply & Installation Pricing REV 1 (VE Changes)

Bid item	Description	Quantity	Unit	Unit Price	Total
Base Bid 022.00	Supply 4" of base material, 1,134 LF of nailer board, 73,578 SF of Soteria 20mm pad TenCate MAXFLO+ 15mm pad, & 73,578 SF of Hellas Matrix Helix 46oz synthetic turf system.	1.000	LS	1,099,000.00	\$1,099,000.00
Base Proposal Total					\$1,099,000.00
Alternate Bid 022.02	Supply and installation of field drainage system inside perimeter of the new synthetic turf field. (EXCLUDES: All ACO trench drain, and SDMH with associated RCP outfall at S end of field, and anything outside of field perimeter.)	1.000	LS	126,000.00	\$126,000.00
Alternates Total					\$126,000.00

BASE SCOPE PRICING INCLUDES THE FOLLOWING:

- 1) Bid acknowledges Addendum 1 and Clarifications 1 & 2.
- 2) This pricing is provided to supply supervision, labor and material for the installation of the synthetic turf system and nailer board package for the Tonopah High School project per request. The complete scope of work is listed below; no other work is included in the total pricing unless specifically listed.
 - a. Supply and install 4" of new base material & provide fine grading to achieve proper planarity per manufacturer standards for new synthetic turf system. **NOTE: Base Scope budget pricing expects subgrade elevation to be left at FG less the turf system and the 4" of base material. There is no pricing in the Base Scope portion of this budget pricing to remove any existing material or for bringing in new or additional subgrade material.**
 - b. Supply & install approximately 1,134 LF of nailer board on concrete curb (PCC curb supplied by others).
 - c. Supply & install approximately 73,578 square feet of ~~SOTERIA™ 20 mm~~ MAXFLO+ 15mm shock pad.
 - d. Supply & install approximately 73,578 square feet of Hellas **MATRIX HELIX 46 oz.** 100% polyethylene twisted monofilament with Shape Memory Technology synthetic turf system with the noted installation options listed below:
 - i. Natural ~~ELIA RENUFILL & REALFILL~~ pea gravel **SBR RUBBER & SAND** infill provided/installed at manufacturers approved infill rates per SF.
 - ii. Supply GMAX & HIC testing.
 - iii. Supply standard 8-year manufacturer warranty supported by a third party insurance policy for the synthetic turf system upon project completion per project specifications.
 - e. Supply an operation and maintenance orientation for care of the synthetic turf field system upon project completion.
- 3) Pricing is based on a standard, 8-hour work shift (normal working hours) at current published Prevailing Wage decision. No overtime, shift, holiday, or weekend pay is included. Union wages are not included and CG&B is not signatory to any union agreements or PLAs for this project.
- 4) One mobilization/demobilization is included in pricing. Anything past that will be charged at \$6,500 per mobilization.

STANDARD EXCLUSIONS:

- 1) Engineering, Permits/Fees, Bonds (outside of adder pricing listed above), QA/QC, Testing, Inspections, Survey, Shop Drawings, Traffic Control, Construction Water/Jones Valve, Sanitary Facilities, Hard Dig, Rock and/or Caliche Removal, Dewatering, Concrete or Asphalt Supply/Installation or Patch Back, Landscape Restoration. (**NOTE: Specific exclusions listed below.**)

SPECIFIC EXCLUSIONS:

- 1) Anything not specifically stated in scope above.
- 2) Permits specific to work or otherwise.
- 3) Demolition of any kind.
- 4) Percolation testing is not included.
- 5) Removal/Replacement of poor or unsuitable soils and/or subgrade stabilization of any kind.
- 6) Supply or installation of any field or sports equipment.
- 7) Fencing.
- 8) Lighting.
- 9) Scoreboards and/or footings for them.
- 10) SWPPP and/or erosion control measures, plans or reporting requirements.

Thank you again for this opportunity! Again, this pricing is provided per the drawings and specifications that were provided at bid time. CG&B is Nevada's leading provider and installer of synthetic turf systems, and we are willing and able to bring this pricing into reality. We certainly do look forward to working with you to get this project installed as quickly and as efficiently as possible. We are available at any time to answer any questions or review this proposal.

*Please also note that due to current economic supply constraints/conditions, this proposal's **material** pricing is valid for a period of no more than 15 days from the date listed above.*

Sincerely,



Jeff Wasson – Lead Estimator, CG&B Enterprises Inc.

M: 725-377-1979 | **E:** j.wasson@cgbinc.com