

Estimate #:260512TM
Date: 5/22/2026
Estimator: Tristen Mathisen
(775) 200-7613
tristen@cheekconstruction.com



3303 Reno Highway Fallon, NV 89406
5401 Longley Ln Suite A18, Reno, NV 89502
Office (775) 426-8802 Fax (775) 867-5939
www.cheekconstruction.com
NV 0078906, 0078907 & CA 1077095

<u>Attention:</u>	CORE Construction		dawnduranleau@coreconstruction.com
<u>Project:</u>	Tonopah HS Sports Complex	<u>Location:</u>	Tonopah, NV
<u>Drawings:</u>	See attached plans	<u>Specs:</u>	4/20/26
<u>Addendum:</u>	1	<u>Prevailing Wage:</u>	2026 Southern Nevada Rural

Proposal Scope of Work

All Equipment, Labor and Material to Form, Place and Finish:

Site Concrete

- Form, pour, and strip Field and Sand Pit Curb
- Form, set wire mesh, pour, and strip throwing pads
- Form, set rebar, pour, and strip Concrete sidewalk
- Sidewalk had no detail so assumed 4"
- Install joint sealant for sidewalk
- Form, set rebar, pour, and strip bleacher footings
- Set bolt templates, set rebar, pour, and grout column baseplates for bleacher spot footings
- Set rebar, pour, and strip light pole bases
- Set flagpole bases
- Set goal post footings
- Set trench drains and catch basins
- Form, pour, and strip trench drains and catch basins
- Set score board bases
- Form, set rebar, pour, and strip NDOT 24" RCP Headwall

Building Concrete

- Layout, form, set rebar, pour, and strip Concession footings
- Tie rebar, place vapor barrier, pour, and sawcut Concessions slab
- Cold weather included for the concession foundation
- Form, set rebar, pour and strip ticket booth pad

Prepwork

- Grade and compact base for field and sand curb
- Grade and compact base for throwing pads
- Grade and compact base for concrete sidewalk
- Dig bleacher footings
- Dig flag pole bases
- Dig goal post bases
- Dig trench drains and catch basins
- Dig score board bases
- Dig concession footings and plumbing
- Grade and compact for concession slab
- Dig for ticket booth pad

Estimate #:260512TM

Date: 5/22/2026

Estimator: Tristen Mathisen

(775) 200-7613

tristen@cheekconstruction.com



3303 Reno Highway Fallon, NV 89406

5401 Longley Ln Suite A18, Reno, NV 89502

Office (775) 426-8802 Fax (775) 867-5939

www.cheekconstruction.com

NV 0078906, 0078907 & CA 1077095

Descope Add 1: Bollards

- Dig hole and set bollards

Descope Add 2: Valley Gutter

- Grade and compact type 2 base for valley gutter
- Form, pour, and strip valley gutter

Descope Add 3: Pole Vault Box

- Form, pour, and strip pole vault box

Descope Add 4: Discus Cage Footings

- Dig footings and setting discus cage footings

Descope Add 5: Away Bleachers Flatwork

- Grade and compact base 6"
- Form, tie rebar, pour, and strip 4" flatwork

Descope Add 6: Additional Drainage Trench

- Dig trench
- Form, pour, and strip and install drainage

Descope Add 7: Bleacher Slab w/ thickened edge

- Dig thickened edge
- Grade and compact slab area
- Form, tie rebar, pour, and strip slab

Descope Add 8: 6'x6' Press Box Footings

- Form, tie rebar, pour, and strip footings
- Dig out footings

Descope Add 9: Concession 6" Flatwork Area

- Pour area with an additional 2" near rollup doors of the concession building

Descope Alt 1: Press Box Slab

- Dig thickened edge
 - Grade and compact base for flatwork area
 - Form, tie rebar, pour, and strip slab
-



General Conditions:

General contractor to provide at no cost to Cheek Construction the following:

Plans, engineering, permits, applications, testing, survey, and inspections necessary for scope of work. Restrooms, dumpsters, and parking for Cheek employees. OSHA approved scaffolding, platforms, and handrails in work areas.

Exclusions:

1. Any work not listed in scope of work above.
2. Costs of bonds, penalties, and/or liquidated damages.
3. Survey, engineering, and permitting costs.
4. Night, weekend, and holiday work.
5. Any specifications, drawings, or addendum not listed above.
6. Offsite parking or parking permits.
7. Concrete washout.
8. Temporary power.
9. Hoisting.
10. Traffic control.
11. Demolition, excavation, shoring of excavation, utilities, backfill, aggregates, BMP's, grading, and compaction.
12. Hydrovac excavation.
13. Vapor barriers and rigid insulation.
14. Concrete encasement for electrical conduits.
15. Trench drains, in slab drains, or other MEP equipment encased in concrete.
16. Pesticides or ground treatments.
17. Footings for traffic signs such as stop signs, parking signs, etc.
18. Fabricated steel, plates, bollards, sleeves, rails, hooks, dowels, bolts, and bolt templates.
19. Epoxy or zinc coatings.
20. Reinforcing couplers or bar splicers.
21. Reworking, cleaning, or cutting of existing reinforcing steel.
22. All welding.
23. Masonry layouts and masonry rebar.
24. Special concrete additives, sealers, hardeners, epoxy coatings, and integral colors.
25. Stamping, polishing, grinding, and exposed aggregate finishes.
26. Caulking and/or joint sealant.
27. All pre-cast concrete.
28. Housekeeping or mechanical equipment pads.
29. Damage to concrete caused by flooding, earthquakes, snow, de-icing agents, and construction equipment.
30. Cold weather protection measures such as concrete accelerators, hot water, and blanket coverage.
31. Fuel surcharges with concrete delivery.

Estimate #:260512TM
Date: 5/22/2026
Estimator: Tristen Mathisen
(775) 200-7613
tristen@cheekconstruction.com



3303 Reno Highway Fallon, NV 89406
5401 Longley Ln Suite A18, Reno, NV 89502
Office (775) 426-8802 Fax (775) 867-5939
www.cheekconstruction.com
NV 0078906, 0078907 & CA 1077095

Payment Terms: Billing on a percentage complete. Payment in accordance with NRS624.624. Not getting paid by a third party (e.g., owner, lender, etc.) does not relieve the party with whom Cheek Construction LLC has been contracted to do work for from getting payment for our work. Receipt of our payment is not predicated solely on our contracted party getting paid first by other third parties. All parties are to be held responsible until payment is received.

The Proposal Price is based upon the Scope of Work, Conditions, and Exclusions listed above. Please read this entire Proposal carefully. Changes to the Scope of Work, Alterations or Conditions may result in additional charges. Changes that result in additional charges will be executed only upon written orders and will become an extra charge over and above the estimate. All change orders must be agreed upon by both the owner and contractor. The foregoing is a limited estimate only based on the information provided and does not account for several factors that could significantly impact this limited offer, including but not limited to, an investigation of the site and/or conditions under which the work is to be performed, neither of which may have been done prior to the communication of this limited offer. This is not an offer nor is it a guarantee and should not be relied upon for any purpose. Cheek Construction LLC expressly reserves the right to change this limited estimate as further information becomes available to it prior to the commencement of work or the execution of a contract or purchase order. Upon acceptance of this Proposal by Customer (indicated by Customer's authorized signature below), this Proposal represents the entire agreement between Cheek Construction LLC and Customer, and supersedes any prior negotiations, representations, or agreements, either written or oral.

Any billed amount that remains unpaid after 30 days from invoice date, could be subject to 1 ½% per month. (18% annual percentage rate). This proposal is valid for 30 days. 4% Courtesy fee applies to all credit card payments.

BASE TOTAL:	\$1,294,656.04
Descope Add 1:	\$6,554.68
Descope Add 2:	\$9,728.06
Descope Add 3:	\$1,622.22
Descope Add 4:	\$6,446.94
Descope Add 5:	\$28,943.73
Descope Add 6:	\$175,782.75
Descope Add 7:	\$111,522.54
Descope Add 8:	\$11,817.68
Descope Add 9:	\$30,338.77
Descope Alt 1:	\$28,877.08
Deduct Light Pole Bases:	\$26,556.43
Deduct NDOT 24" RCP Headwall	\$16,876.72

Estimate #:260512TM
Date: 5/22/2026
Estimator: Tristen Mathisen
(775) 200-7613
tristen@cheekconstruction.com



3303 Reno Highway Fallon, NV 89406
5401 Longley Ln Suite A18, Reno, NV 89502
Office (775) 426-8802 Fax (775) 867-5939
www.cheekconstruction.com
NV 0078906, 0078907 & CA 1077095

In acceptance of this bid please sign and date below.

Name: _____

Date: _____

Thank you for the opportunity to provide you with a proposal for your project. Should have any questions, please do not hesitate to call. Thank you.

Regards,

Kyle Cheek

Kyle Cheek - Owner

All installed material is guaranteed to be as specified. All work to be completed in a professional manner according to standard practices. All agreements contingent upon strikes, accidents, or delays beyond our control. Our workers are fully covered by Workman's Compensation Insurance. All work is guaranteed for one full year.

Under normal conditions, reinforced concrete and post-tensioned concrete develop cracks. The cracks are due to the inherent shrinkage of concrete, creep, and the restraining effects of other structural elements. The cracks formed typically do not directly affect concrete's serviceability or strength. The use of additives can enhance performance however cracking can still occur.