



Bid Proposal

May 22, 2026

To: **Core Construction**
Attn: **Jon Cox**

Project: **NCSD – Tonopah High School Sports Complex – Descope revision**

M & H Building Specialties, Inc. is pleased to submit our proposal for the above referenced project. Our proposal is based on drawings and specifications by KNIT dated 4/20/2026, including Addendum 1, Clarification 1,2. This proposal is subject to the following inclusions, qualifications and exclusions:

Scope of Work

Metal Framing & Drywall.....	\$182,189.00
Acoustical Ceilings	\$18,981.00
FRP Panels.....	\$26,954.00
Painting & Finishes.....	\$47,135.00

TOTAL AMOUNT	\$275,259.00
---------------------	---------------------

If payment & performance bond is required, ADD 1%

ADD Alternates

1. Cornerguards	ADD \$21,018.00
-----------------	------------------------

DEDUCTIVE Alternates

1. ACT Combined deduct	DEDUCT (\$2000.00)
------------------------	---------------------------

Descope Items

1. T.O.W Caulking	ADD \$5,351.00
2. Kitchenzone in lieu of Cleanroom ceiling tiles	DEDUCT (\$1,823.00)
3. Insulation	ADD \$26,248.00



Inclusions

Metal Framing & Drywall:

1. Frame new exterior soffits as shown
2. Frame new interior walls, ceilings and soffits as shown
3. Frame metal stud jambs and headers as shown
4. Furnish and install 6" metal backing for grab bars, toilet accessories
5. Install access doors (supplied by others)
6. Acoustical sealant at base of wall
7. Furnish and install 5/8" Type X drywall throughout
8. Furnish and install 5/8" Dens Shield at walls scheduled to receive FRP
9. Furnish and install 5/8" Dens Glass sheathing at exterior soffits
10. Level 3 finish throughout, fire tape above ceilings
11. All exposed drywall to receive splatter texture

Acoustical Ceilings:

1. Furnish and install Armstrong 2712 Dune 2 x 4 tile with standard 15/16" white grid
2. Furnish and install Armstrong 870 Cleanroom VL 2 x 4 tile with standard 15/16" white grid
3. Furnish and install two (2) wires per light fixture within ACT ceiling system
4. Based on being able to attach directly to deck above

FRP Panels:

1. Furnish and install white textured FRP panels with matching vinyl trims in Kitchen 8' AFF
2. Furnish and install drak grey textured FRP panels with matching vinyl trims in restrooms 8' AFF

Painting & Finishes:

1. Utilization of Sherwin Williams paint products
2. All painting to be done before acoustical ceilings, millwork, wood doors and fixtures are installed
3. Paint exposed drywall walls and ceilings (1 coat primer followed by finish coats)
4. Paint of hollow metal doors and frames
5. Paint of exposed deck (1 color – All items are to be installed within the open ceiling prior to painting of exposed structure)
6. Anti-graffiti coating at exterior CMU of concession/restroom building

Qualifications

1. This proposal has been priced based on a start date of 2/8/27 with a duration of 7 months
2. Work is figured to be done during normal business hours
3. All equipment, lifts and hoisting necessary to complete our scopes of work are included
4. Delegated design engineering for light gauge framing is not included
5. Layout is included for our scopes of work only



Exclusions

1. Climate control of building or site
2. Remobilization due to delays by other trades
3. Dumpsters, debris haul-off and associated fees
4. Parking fees
5. Temporary utilities for construction
6. Overtime, night or weekend work
7. Repair of damage by other trades
8. Bonding costs
9. Engineering and shop drawings for light gauge framing
10. Firesafing/firecaulking
11. Sound or thermal insulation at walls and roof structure
12. Rigid insulation or Z furring
13. Acoustic caulking at top of wall or MEP penetrations
14. Caulking and backer rod at dissimilar surfaces
15. Waterproofing membrane or vapor barrier
16. Metal flashing at any location
17. Wood framing, blocking, sub-tops or nailers for roof coping
18. Access panels
19. G90 galvanized coatings
20. Non-gauge miscellaneous steel
21. Support wires for MEP items
22. Unistrut support systems
23. Expansion joints and covers
24. Cornerguards – See alternate
25. Install of signage or graphics
26. Floor finishes or sealers
27. Painting of metal roof coping or flashing

This proposal shall be incorporated into and become a part of a standard construction contract document by addendum, attachment or exhibit for the purpose of defining inclusions, exclusions and qualifications. We reserve the right of refusal to accept any contract for scope of work less than the complete base bid total. This proposal is based on a mutually developed and agreed upon construction schedule with all activities being performed in a logical sequence. Any changes to the schedule which result in work that is out of sequence shall incur additional costs. All building lay-out control lines and elevation benchmarks and MEP locations shall be provided by the General Contractor. Any touch-up of paint after final coat will incur additional costs. This proposal provides for remediation of deficiencies in Work for one (1) Punch-list as prepared by the Owner. Any and all additional punch-list work will incur additional costs and time. M&H Building Specialties accepts no responsibility for delays or associated costs for trade damage to our finished work, MEP inspection delays, Owner changes or GC changes to the contract documents.

Nevada Contractor's License Numbers

Carpenters 0015400 Type C-3, Painters 0041010 Type C-4, and Plasterers 0051255 Type C-17, each classed as Unlimited

WE RESERVE THE RIGHT OF REFUSAL TO ACCEPT ANY CONTRACT OF SINGLE SCOPES WITHOUT BEING AWARDED METAL STUD FRAMING AND DRYWALL.

THIS PROPOSAL IS VALID FOR Thirty (30) DAYS AFTER WHICH TIME WE RESERVE THE RIGHT TO REVISE, ALTER OR AMEND THIS PROPOSAL.



Respectfully Submitted,
Jason Bise

A handwritten signature in blue ink, appearing to read 'JB' or 'Jason Bise'.

Estimator
M & H Building Specialties, Inc.