



2667 W. Cheyenne Ave
N. Las Vegas, NV 89032
702-438-7426
 NV License #0029174A

To:	CORE Construction Services of Nevada	Contact:	
Address:	7150 Cascade Valley Ct Las Vegas, NV 89128	Phone:	(702) 794-0550
Project Name:	NCSD THS Sport Field Replacement-(U)	Fax:	
Project Location:		Bid Number:	
		Bid Date:	5/12/2026

Item #	Item Description	Estimated Quantity	Unit	Total Price
1	Mobilization	3.00	EACH	\$17,202.18
Total Price for above Items:				\$17,202.18
Water				
2	Furnish Install 2" Schd.40 PVC	115.00	LF	\$12,315.35
Total Price for above Water Items:				\$12,315.35
Sewer				
3	Furnish & Install 4" SDR-35 PVC. Includes Core Into Existing SSMH	115.00	LF	\$23,922.30
4	Provide & Place 48" SSMH	1.00	EACH	\$18,218.70
Total Price for above Sewer Items:				\$42,141.00
Storm Drain				
5	Provide & Place 48" SDMH Type I	1.00	EACH	\$17,048.96
6	Furnish & Install 24" RCP. Includes Headwall	145.00	LF	\$64,327.80
7	Furnish & Install 8" HDPE Perforated Pipe. Includes Drain Rock & Geofabric	815.00	LF	\$153,562.30
Total Price for above Storm Drain Items:				\$234,939.06
Hard Rock				
8	Caliche Allowance For This Scope Of Work	1.00	LS	\$29,674.10
Total Price for above Hard Rock Items:				\$29,674.10
Demolition				
9	Demo Exiting Wet Utilities	1.00	LS	\$34,087.66
Total Price for above Demolition Items:				\$34,087.66
Misc				
10	Export Spoils From Scope Of Work	1.00	LS	\$11,626.64
11	Adjust SSMH To Final Grade	2.00	EACH	\$5,525.58
Total Price for above Misc Items:				\$17,152.22
Total Bid Price:				\$387,511.57
Field Drainage				
Alt. 1	Furnish & Install ACO Slot Drain Sport System 3000. Includes 6ea. Catch Basins.	560.00	LF	\$113,870.40
Alt. 2	Furnish & Install 4" Perforated Pipe For Long Jump/Triple Jump Sand Pit	1.00	LS	\$25,071.80
Total Price for above Field Drainage Items:				\$138,942.20
Homework				
HW	Deduct If We Can Leave Spoils Onsite	1.00	LS	(\$2,949.57)



2667 W. Cheyenne Ave
N. Las Vegas, NV 89032
702-438-7426
NV License #0029174A

To: CORE Construction Services of Nevada	Contact:
Address: 7150 Cascade Valley Ct Las Vegas, NV 89128	Phone: (702) 794-0550
Project Name: NCSD THS Sport Field Replacement-(U)	Fax:
Project Location:	Bid Number:
	Bid Date: 5/12/2026

Item #	Item Description	Estimated Quantity	Unit	Total Price
HW	Provide A Trenching Machine For 1 Week. Includes Mobilization.	1.00	LS	\$19,897.86
Total Price for above Homework Items:				\$16,948.29

Notes:

- Exclusions;
Overtime Inspections. Hard Rock Removal / Disposal.
Asphalt or concrete patching.
Unknown underground structure demo.
Building connections.
Permits, drawings, engineering, testing or survey.
Bollards. Cost of water. Night Work. FDC. BWV.
Traffic Control. Material cost escalation.
Electrical
Telecomm
Sand for sand pits.

* Utility Material pricing will be adjusted by review of proposals from supplier from Bid Date to Purchase Date.

Due to ongoing volatility in asphalt and fuel markets, if fuel prices exceed \$4.00 per gallon
<https://www.eia.gov/petroleum/gasdiesel/>,
we reserve the right to adjust our pricing to reflect any additional cost impacts at the time the work is performed.

NVCL 29174A
Bid Limit 4.5Mil

ACCEPTED: The above prices, specifications and conditions are satisfactory and are hereby accepted. Buyer: _____ Signature: _____ Date of Acceptance: _____	CONFIRMED: NDX, LLC Authorized Signature: _____ Estimator: Giovanni Lopez 702-438-7426 glopez@ndxllc.com
---	--



**2667 W. Cheyenne Ave
N. Las Vegas, NV 89032
702-438-7426**

To:	CORE Construction Services of Nevada	Contact:	
Address:	7150 Cascade Valley Ct Las Vegas, NV 89128	Phone:	(702) 794-0550
Project Name:	NCS D Tonopah HS Sports Complex (G)	Fax:	
Project Location:	1 Ray Tennant Wy, Tonopah, NV	Bid Number:	
Addendum #:	3	Bid Date:	5/12/2026

Item #	Item Description	Estimated Quantity	Unit	Total Price
1	Mobilize	2.00	EACH	\$17,883.14
2	Demolish Sod, Turf, Light Pole Bases, Fence, Buildings, Track, Trees & Curbs.	1.00	LS	\$683,842.12
3	Overexcavate For Proposed Building Pad.	1.00	LS	\$11,351.06
4	Mass Grade Site & Export Approx 18,500 Cy To Offsite Location.	1.00	LS	\$947,913.90
5	Cut Subgrade And Provide Type II For Mow Curb.	1,300.00	LF	\$28,262.00
5	Provide And Place 2" Of Asphalt Over 4" Of Aggregate For Access Road.	29,000.00	SF	\$194,300.00
6	Provide And Place 4" Asphalt Over 4" Of Type II For Running Track And Field Event Areas. (1 Mob For Paving)	69,100.00	SF	\$620,518.00
7	Provide And Place Rock For Laydown Yard.	10,000.00	SF	\$23,000.00
8	Provide SWPP Plan And Controls	1.00	LS	\$25,120.78
9	Caliche Allowance For This Scope Of Work.	480.00	CY	\$27,316.80
10	Provide And Place 6" Of Type II For Sidewalks And Building Pad.	1,012.00	TON	\$78,136.52
11	Provide And Place 4" Of Drain Rock Under Turf Area	74,220.00	SF	\$106,876.80
Total Price for above Items:				\$2,764,521.12

Alternates

Alt 8.01	Discount If Awarded Building Wrecking	1.00	EACH	\$6,000.00
Alt 8.02	Caliche Unit Rate. Remove And Replace With Engineered Fill	1.00	CY	\$46.00
Alt 8.03	Add For Demolition At Elementary School Campus. Demolish Existing Buildings And Canopy. Leave Concrete Building Pads And Wall. Includes Dump Fees And Transportation Costs To The Beaty Landfill. Provide Dust Palliative To Disturbed Areas. Asbestos Abatement	1.00	LS	\$1,498,400.00
Alt 8.04	Provide And Place 2" Of Sand And Geo-liner Under Turf Area	74,220.00	SF	\$156,604.20
Total Price for above Alternates Items:				\$1,661,050.20

Homework

HW	Add To Apply Herbicide Under Asphalt Areas	99,000.00	SF	\$20,790.00
HW	Deduct For Geoliner From Alt 8.04	1.00	LS	(\$49,752.77)
HW	Deduct If We Can Leave Spoils Onsite	1.00	LS	(\$209,082.55)
Total Price for above Homework Items:				(\$238,045.32)

Total Bid Price: \$4,187,526.00

Notes:

- Exclusions;
Clean up/ haul off behind other contractors
Hard Rock removal or disposal
Placement of Concrete / Slurry.
Permits, drawings, engineering, testing or survey
Traffic Control. Cost of water, SWPP
Excavating / backfill of footings. Erosion control maintenance
Striping, signage, bumper blocks or speed bumps.
Soil sterilant, termite control, weed killer, herbicides.
Supply or placing topsoil, dewatering
Sand under Turf
Sports Pit Material. Javlin Runway Mix
Walls

Bond Rate is 2%

Asphalt pricing and Utility Material pricing shall be adjusted at time of placement. Asphalt Pricing shall be reviewed from Bid Date to Pave Date per
NDOT website for POTEN, <https://www.dot.nv.gov/home/> . Utility Material pricing will be adjusted by review of proposals from supplier from Bid
Date to Purchase Date.

NVCL 29174A
Bid Limit 4.5Mil

ACCEPTED:

The above prices, specifications and conditions are satisfactory and
are hereby accepted.

Buyer: _____

Signature: _____

Date of Acceptance: _____

CONFIRMED:

NDX, LLC

Authorized Signature: _____

Estimator: Bianca Soriano Ozuna
702-438-7426 bsoriano@ndxllc.com