



QUANTUM ELECTRIC, LLC

3151 MANZANITA LN.
ELKO, NEVADA 89801

PHONE: (775) 777-2000

quantumelectric@frontiernet.net

TO: Core Construction

DATE: 6/1/26

ATTN: Dawn Duranleau

RE: Tonopah High School Sports Field Replacement Rev 4

We hereby propose to complete the referenced project as follows: Electrical per drawings E000, E001, E002, E003, E004, E005, E010, E011, E012, E013, ED110, ED310, E110, E210, E300, E310, E320, & E410 dated 4/20/26 and Div. 26 & 27 specifications.

***Acknowledgement of Addenda #1 and Clarifications #1&2.**

INCLUSIONS: Items included under this proposal.

- Supply and install of building lighting and lighting controls per plans.
- Supply and install of Musco sports lighting and lighting controls per plans.
- Supply and install on new panel CB, mini-power zone panel PB, 5KVA transformer, (2) TVSS, new breakers in existing switchboard, and disconnect switches per plans.
- Remove existing power service to Concession Building, Press Box, and scoreboard.
- Remove circuiting and speakers on existing wood light poles. Remove and dispose of wood poles.
- Junction boxes and conduit to accessible ceiling for CCTV, data, and speakers. Underground conduits for data, speakers, and future fire alarm.
- Any associated conduit, wire, cable, junction boxes, wiring devices, and terminations per plans.
- Temporary power. (Temporary lighting if applicable not included).
- Supply and install CAT6A/OSP fiber between new building and existing school.
- Supply and install of new speakers and horns in Concession per plans.
- Supply and install all CAT6A and CAT6 cabling and jacks per plans.
- Remove existing pole field sound system and reinstall on new poles and in press box. (We cannot guarantee the Sound system quality since existing equipment will be reused. No existing equipment shown in pictures allows for any adjustments beyond volume).
- Install owner supplied cameras.
- Lift equipment.
- Storage container.
- Crane to stand sports light poles.
- Excavation and backfill for electrical trenching using conventional excavation equipment. Excavate around existing wood poles for removal.
- Prevailing wages applied.
- Textura fee included.
- **Hard Dig Alternate 01:** T&M rate to supply 60,000 lb excavator and hydraulic hammer for rock excavation.
- **Alternate 103.01:** Electrical Demo at Elementary School. (See separate proposal).
- **Deductive Alternate 03:** Remove Showlight & RGBW option from Musco poles.
- **Deductive Alternate 04:** Remove lights, receptacles, branch circuit conduits, and wire for Press Box.
- **Alternate 05:** Electrical excavation 100% hard dig.
- **Alternate 06:** Concrete foundations for (4) Musco poles. (Excavation excluded).
- **Deductive Alternate 07:** Remove (2) 2" conduits from existing high school to low voltage junction boxes at sports field. Remove OSP CAT 6 and 6-Strand MM fiber optic cable. Delete excavation based on regular digging conditions.



QUANTUM ELECTRIC, LLC

3151 MANZANITA LN.
ELKO, NEVADA 89801

PHONE: (775) 777-2000

quantumelectric@frontiernet.net

-
- **Deductive Alternate 08:** Same as Deductive Alternate 07 except based on 100% hard dig conditions.

EXCLUSIONS: Items not included under this proposal.

- Any permit or utility fees.
- Any temperature controls.
- Any fire alarm. (Not applicable).
- Excavation and concrete for Musco light pole foundations.
- Hard rock excavation. (See alternate add pricing if applicable).
- Configuration of new camera system and paging/intercom to work with existing system. (By NCSD).

State of Nevada Contractors License No.: **0092278**

Base Electrical Price: \$937,714.00

Hard Dig Alternate: \$735.00 per cubic yard (T&M rate).

Alternate 103.01: \$41,564.00

Deductive Alternate 03: <-\$9,355.00>

Deductive Alternate 04: <-\$6,144.00>

Alternate 05: \$71,516.00

Alternate 06: \$33,102.00

Deductive Alternate 07: <-\$37,069.00>

Deductive Alternate 08: <-\$48,702.00>

OFFERED BY: _____ ACCEPTED BY: _____ DATE: _____

Joe Curry

Electrical Construction Manager / **VOID IF NOT ACCEPTED WITHIN 30 DAYS**