



Lic #53181 (C-10 Landscape) Lic #63605 – (C-5 Concrete) Lic#51522 (A- General Engineering)
Monetary Limit – Unlimited

Landscape Proposal

5/20/26

To: Core Construction

Project: NCSD – Tonopah High School Sports Complex
Scope: Landscape, Irrigation & Synthetic Turf

Tand Inc. hereby agrees to provide labor, materials, equipment and tools necessary to complete the Landscape and Irrigation as described below. Plans: SLA, Planting & Irrigation, dated 4/20/ 26. Clarifications #1 & 2 noted. Addenda #1 noted.

Prevailing Wage Rates Included

Landscape & Irrigation – Scope of Work:

1. Ground Treatments:
 - Pre Emergent Weed Control
 - Landscape DG @ 2" depth – Color & size to match existing (Add Alt)
2. Temp Tree Protection:
 - Supply & Install Temp Water
 - Supply & Install Tree Protection for Trees @ South Edge of Running Track
 - 40 Man Hours for Unforeseen Irrigation Repairs & Hand Watering
3. 6 Month Post Install Maintenance & Warranty Period
4. Irrigation System:
 - Tie Into Existing Functional System
 - Provide & Install Irrigation for Trees @ South Edge of Running Track
 - Mainline, Sleeve & QC Valves

Synthetic Turf Scope of Work:

1. 73,531 SF of Synthetic Turf – Approved Manufacturer per spec
2. Base Material – Product Approved by Manufacturer
3. Nailer Boards
4. Includes Game Markings – Lines, Center Logo & End Zone Letters
5. Geotex Fabric, Underlayment Pad & Infill
6. GMAX Test & 8 Year Insured Warranty
7. Field Groomer – Turnover Item

Athletic Equipment Scope of Work:

1. Football Goal Posts – Footing, Flags & Padding
2. Pole Vault Equipment – Landing System, Pit Box & Lid, Base Pads, Crossbar & Accessories
3. Long/Triple Jump – Sand Catchers & Pit Sand
4. High Jump – Equipment & Landing System
5. Discus & Shot – Concrete Pad, Toe Board & Rings
6. Discus Cage – Posts, Netting & Ground Sleeves
7. Shot Put & Discuss Runway Mix & Rubber Edging
8. Scope includes Fasteners, Spare Parts & Footings

Exclusions/Clarifications:

1. Rough grade to be provided and field verified at +/- 0.10 ft.
2. Tand Inc is not responsible for damages made to existing landscape caused by others. Repairs, replacement, temp irrigation and/or hand watering due to damages by others is excluded.
3. Sleeving access required prior to all hardscape.
4. Water for dust control, track out pad, & engineering, testing or surveying by others.
5. This bid excludes demolition of any kind, track surfacing, catch basins or slot drainage, hardscape, pavers & curbing. Items not specifically listed in our proposal are excluded.
6. Soccer goals were not identified in the drawings & specs. This item is excluded.
7. Full access to work area required. Staging area required.
8. Field trenching under synthetic turf by others.

Proposal Package #16 - Landscape & Irrigation **\$163,800.00**

Add Alternate #02 016.02 - Decorative Rock Groundcover **\$9,500.00**

35 Ton Allowance – Color & Size to match existing

Proposal Package #22 - Synthetic Turf System **\$1,008,700.00**

Proposal Package #19 - Track & Field Equipment **\$511,400.00**

***All Options include P&P Bond**

Mike Barney

Mike Barney
Landscape Estimator
Cell (702) 429-9178

**4500 VANDENBURG DRIVE
NORTH LAS VEGAS, NV 89081
PHONE: 702-889-4676 FAX: 702-889-8876**