

Dawn Duranleau

From: Tyler Bruinekool <tyler.bruinekool@musco.com>
Sent: Monday, May 11, 2026 8:20 PM
To: Dawn Duranleau
Subject: RE: Structural/Installation Concern Tonopah High School
Attachments: 70 C base.jpg

The section Highlighted in red is the base that is going to be needed for the poles. I can let the EC's know if you would like if none of them have submitted there bids yet. As they will all likely be carrying this in there number since Musco will be providing the base. The biggest thing is the rebar cage that structural is going to be calling out now to reinforce our precast base. Let me know how you would like me to proceed. I took this from another project but this is very similar if not the same.

Thanks,

Tyler Bruinekool
Nevada Field Sales
Sales Representative
641-638-4071

POLE FOUNDATION SCHEDULE (SEE LIGHT POLE FOUNDATION DETAIL A/C3)

TYPE	ASD GROUNDLINE FORCES (MAXIMUM)			C.I.P. DEEP FOUNDATION				PRECAST BASE
	MOMENT (M) KIP-FT	SHEAR (V) KIPS	VERTICAL (P) KIPS *	DIAMETER INCHES	EMBEDMENT FEET	VERTICAL REINFORCING (ASTM A615 GR 60)	HOOP TIE SIZE & SPACING (ASTM A615 GR 60)	EMBEDMENT FEET
LSS40-A	14.660	0.616	0.643	36"	8'-0"	8-#8	#4 @ 6" O.C.	8'-0"
LSS60-AA	30.280	0.903	1.068	36"	10'-0"	8-#8	#4 @ 6" O.C. TOP 9'-0" & #4 @ 12" O.C. BELOW	10'-0"
LSS70-AA	40.920	1.000	1.258	36"	10'-0"	8-#8	#4 @ 6" O.C. TOP 9'-0" & #4 @ 12" O.C. BELOW	10'-0"
LSS70-A	48.630	1.204	1.606	36"	12'-0"	8-#8	#4 @ 6" O.C. TOP 9'-0" & #4 @ 12" O.C. BELOW	12'-0"
LSS70-B	59.190	1.442	1.887	36"	12'-0"	8-#8	#4 @ 6" O.C. TOP 9'-0" & #4 @ 12" O.C. BELOW	12'-0"
LSS70-C	73.050	1.704	2.550	36"	14'-0"	8-#8	#4 @ 6" O.C. TOP 9'-0" & #4 @ 12" O.C. BELOW	14'-0"

From: Dawn Duranleau <dawnduranleau@coreconstruction.com>
Sent: Monday, May 11, 2026 4:52 PM
To: Tyler Bruinekool <tyler.bruinekool@musco.com>
Subject: Re: Structural/Installation Concern Tonopah High School

I appreciate you working on that.

Thanks!

Dawn Duranleau, AIA, CCM, LEED GA
PreConstruction Manager

CORE Construction | West
C: [702-467-0560](tel:702-467-0560) | W: coreconstruction.com

From: Tyler Bruinekool <tyler.bruinekool@musco.com>
Sent: Monday, May 11, 2026 7:50:48 PM
To: Dawn Duranleau <dawnduranleau@coreconstruction.com>
Subject: RE: Structural/Installation Concern Tonopah High School

Dawn,

I am trying to get that Info ASAP I will send it over to you as soon as I have it. Again sorry about this, with the last minute change updating the structural clearly slipped through the cracks.

Thanks,

Tyler Bruinekool
Nevada Field Sales
Sales Representative
641-638-4071

From: Dawn Duranleau <dawnduranleau@coreconstruction.com>
Sent: Monday, May 11, 2026 4:48 PM
To: Tyler Bruinekool <tyler.bruinekool@musco.com>
Subject: Re: Structural/Installation Concern Tonopah High School

Hi Tyler,

Thank you for bringing this to my attention. Do you have preliminary footing requirements for the updated Design? I can work with my concrete subs to pick up correctly.

Thanks,
Dawn

Dawn Duranleau, AIA, CCM, LEED GA
PreConstruction Manager

CORE Construction | West
C: [702-467-0560](tel:702-467-0560) | W: coreconstruction.com

From: Tyler Bruinekool <tyler.bruinekool@musco.com>
Sent: Monday, May 11, 2026 7:42:29 PM
To: Dawn Duranleau <dawnduranleau@coreconstruction.com>
Subject: Structural/Installation Concern Tonopah High School

Dawn,

I know this is way late and I apologize but just had another concern I came across for the Tonopah Bid. The foundation assembly schedule that is being shown in the bid was from the structural before we were asked to add fixtures to the poles to light the track and before we had the geo-tech. I apologize again usually I get the plans when these projects go out to bid but this time I only received them from a contractor last Thursday afternoon.

With the Geo-tech and the added fixtures structural is now calling for reinforced bases which I am guessing none of the contractors are including in there bid for the installation at this time. I know with the submittals we will have to have the stamped structural design provided and with what is currently being bid for the foundation is not corrected for the addition of fixtures to light the track. Not sure if there is anything that can be done now but wanted to at least bring it to your attention.

Thanks,

Tyler Bruinekool
Nevada Field Sales
Sales Representative
641-638-4071