



NVCL#s 75964, 75965, 75966 • CACL# 1015375

1315 Financial Blvd Reno, NV 89502
 775-332-0602 Office 775-562-2693 Fax
 Bid Limit \$4,500,000

To: CORE Construction
 Address: 5330 Reno Corporate Dr
 Attention: Dawn Duranleau
 Phone: (702) 926-1812
 Fax:
 Email: dawnduranleau@coreconstruction.com

Job Name: Tonopah HS Sports Complex
Job Location: 1 Ray Tennant Way
Estimator: Luis Hernandez

Bid # 13390

Base Bid Description: Waterproofing, Caulking, Epoxy Flooring, Sealed Concrete

Scope of Work	Manufacturer	Style	Color
<u>Below-Grade Waterproofing</u>	Grace	Bituthene 3000	Black line
Below-Grade Insulation	Owens Corning	Foamular 250 2"	Pink
<u>Sealed Concrete</u>	Euclid Chemical	Everclear Vox	Clear
Caulking At Saw-Cut Joints	Sika	HY 100	TBD
<u>4" Rubber Base</u>	Roppe	Contours Simplicity	123 Charcoal
<u>Epoxy Flooring</u>	Dur-A-Flex	Dur-A-Chip	Scarlet - Macro Chip
6" Epoxy Cove Base	Dur-A-Flex	Dur-A-Chip	Scarlet - Macro Chip
<u>Site Caulking</u>	Sika	HY 100	TBD
<u>CMU Joint Caulking</u>	Sika	2CNS EZ Mix	TBD
<u>Hollow-Metal Door Caulking</u>	Sika	2CNS EZ Mix	TBD
<u>GWB To CMU Caulking</u>	Sika	2CNS EZ Mix	TBD
<u>Metal To CMU Caulking</u>	Sika	2CNS EZ Mix	TBD

Exterior Building Penetrations Caulking	Sika	2CNS EZ Mix	TBD

Below-Grade Waterproofing	\$	33,150.00
<i>Includes 2" Insulation Board</i>		
Sealed Concrete	\$	18,035.00
<i>Includes Saw-Cut Joint Caulking</i>		
4" Rubber Base	\$	4,860.00
Minor floor prep & Schluter strip included. Epoxy Flooring	\$	62,680.00
<i>Includes 6" Epoxy Cove Base</i>		
- Luis Hernandez, 05/26/26 Site Caulking	\$	20,300.00
CMU Joint Caulking	\$	4,530.00
Hollow-Metal Door Caulking	\$	7,350.00
GWB To CMU Caulking	\$	15,890.00
Metal To CMU Caulking	\$	8,050.00
Exterior Building Penetrations		
Caulking	\$	6,300.00

Proposal Notes (Clarifications & Exclusions):

Below-Grade Waterproofing/Insulation

Clean Foundation Walls & Footings then apply Grace Bituthene 3000 Waterproofing System on Exterior Foundation Wall and Footings *GC To Snap Below-Grade Waterproofing Lines*

Furnish & Install Owens Corning 2" Insulation Board Once Below-Grade Waterproofing Has Been Installed

This System Includes the Following:

Bituthene Primer On Foundation Walls and Footings

Followed Up a Cant Bead of Liquid Membrane on Stem Wall and Footing Joint

Apply Waterproofing Membrane to Exterior Foundation Wall and Footings

After, Apply Insulation Board To Waterproofing Membrane

Once Complete Add Drain Board Over Insulation Board For A Complete Waterproofing System

Excludes Any Metal Flashing, Underslab Vapor Barrier, Concrete Wall Patching, Nail Removing

Sealed Concrete

Furnish & Install Water-Based Concrete Sealer At SC-1 Areas

Furnish & Install Caulking At Saw-Cut Joints In Sealed Concrete Areas

Excludes Concrete Grinding, Crack Repair, Minor Floor Prep Included, Schluter Strip Included

Rubber Base

Furnish & Install 4" Rubber Wall Base At RB-1 Areas

Epoxy Flooring

Furnish & Install Dur-A-Flex Dur-A-Chip Epoxy Flooring At EP-1 Areas

Furnish & Install 6" Epoxy Cove Base

Excludes Sloping, Major Concrete Prep, Minor Floor Prep Included

Caulking

Furnish & Install Sika HY 100 Caulking At Exterior Site Concrete Expansion Zip-Cap Joints
Furnish & Install Sika 2CNS EZ MIX Caulking At CMU Vertical Interior/Exterior Joints
Furnish & Install Sika 2CNS EZ MIX Caulking At Hollow Metal Doors Inside & Out
Furnish & Install Sika 2CNS EZ MIX Caulking At Gypsum Wall Board To CMU Joint
Furnish & Install Sika 2CNS EZ MIX Caulking At Exterior Metal To CMU Joint
Furnish & Install Sika 2CNS EZ MIX Caulking At Exterior Building Penetration Joints
Excludes Caulking Storefronts, Any Other Joints Not Called Out Above

Excludes Any Floor Protection After Material Has Been Installed

Prevailing Wage Rates Apply
Bid Assumes Normal Working Hours
Perform Normal Prep

No Prevailing Wage Pricing is included, unless specified, in writing, above
Excludes:

Major floor prep, alkalinity remediation & moisture block
Abatement, demo & disposal done by others (if needed)
Moving furniture, fixtures, plumbing, partitions, equipment, stalls and other objects in area of scope to be done by others
Mortar bed for floor, drywall repairs, paint touch ups, underlayment, and tile backer board (if required)
Wall base/floor finish protection, potable water and electricity provided by others
Floor protection during work in place included BUT excluded after scope completion
Remobilization, restaging fees & final cleaning
Any other scope of work other than listed above

NOTE: All flooring installations performed during cold weather months must be in an enclosed building, with the HVAC system operational, between 65 degrees to 90 degrees Fahrenheit, throughout the day and evening hours, for at least 72 hours before, during & after the installation. Non-compliance may affect the installation warranty.

***Due to Material and Freight Instability, Proposal is Valid for 30 days from Date of Proposal ***

***SILegacy Floor Finishing may extend beyond 30 days at it's own discretion ***

Excludes additional costs related to Owner or Contractor-required software for Billing, pre-approval processes, or safety Software requirements.

Any such costs, will need to be added to the cost of the job.

Signature *Luis Hernandez*
Name Luis Hernandez
Date 5/26/2026

Acceptance Signature _____
Name _____
Date _____

***Due to Material and Freight Instability, Proposal is Valid for 30 days from Date of Proposal ***

***SILegacy Floor Finishing may extend beyond 30 days at it's own discretion ***