

Corporate Office:
3566 Polaris, Suite #1
Las Vegas, NV 89103

NV License #: 53782 C-5
\$3.1M Limit



**RYERSON
CONCRETE**
STRUCTURAL | SPECIALTY COATINGS | POLISH

Office (702) 251.0539
Fax (702) 995.4900
www.RyersonConcrete.com
CA License #: 1009772 C-8
Unlimited Limit

General Contractor

Core Construction
NV OFFICE

Project Name

NCSD THS Sports Field Replacement
170 E Ray Tenant Ln
Tonopah NV 89049

Customer Contact: Dawn Duranleau
Office Number: 702.926.1812
Fax Number:
Email Address: dawnduranleau@coreconstruction.com

Ryerson Estimator: Kenny Ryerson
Proposal Number: 26-0207
Today's Date: June 2, 2026
Date Of Plans: PER EMAIL

Epoxy Flooring Proposal

Proposal includes labor & materials (u.n.o.) for the following items/scope- per plans (dated above) & specs as shown:

Sealed Concrete System Specifications

Approx. 2,650 SqFt \$32,493.00

Designated areas to be cleaned with walk-behind or ride-on scrubbers as first step to prepare substrate to receive new finishes.
All drywall mud, paint, plumbers glue, caulk lines, etc. to be removed by others prior to Ryerson Concrete mobilization.
Furnish & install clear concrete sealer per manufacturer's instructions.
All caulking around drains, floor sinks, electrical boxes by others (plumber/electricians).

- * Base bid DOES include filling all expansion joints (with epoxy mortar mix), cracks, and patches prior to coating application.
- * Base bid DOES include installation & caulking of rubber base.
- * Building must be climatized and environmental conditions must be met prior to installation per manufacturer's instructions
- * Base bid does NOT include sloping to drains. IF slope is needed, change order to be issued prior to commencement
- * Any additional Tariffs will be charged to the owner.
- * Base bid DOES NOT include transition/Schluter strips..

Add/Alt: Supplying Sufficient Power to run Equipment \$2,508.00
3 Phase 480 V 50 AMP Power

ADDENDUMS NOTED: 1 & 2

NOTES / CLARIFICATIONS:

1. Unless otherwise noted, Ryerson Concrete is not responsible for floor protection after completion of work.
2. Base bid only includes normal working hours 6am-2:30pm M-F. Any weekend or overnight work required or preferred to complete scope of work on expedited schedule will result in a change order.
3. All environmental conditions are to be met per manufacturer's guidelines. Ryerson Concrete will not proceed with any installation if conditions cannot be met or are unsatisfactory.
4. Part of our preparation may raise concrete dust. If any site equipment is sensitive to this dust, it is advisable that such equipment be covered prior to Ryerson Concrete's start of work. Ryerson Concrete will not assume any responsibility.
5. If applicable, customer understands that the dye/stain color is a direct result of the concrete substrate and that the final color cannot be guaranteed.
6. The General Contractor or Customer is responsible for posting notice to all employees and/or subcontractors to stay clear of the specified working area(s) during the application process.
7. Should Ryerson Concrete be delayed at any time during the progress of the project, either by the customer, a separate contractor employed by the customer, labor disputes or by any causes beyond our control, then the time requirements for the project and price will be adjusted by a Ryerson Concrete change order.
8. The customer is responsible for providing: 120v power, 240v, & 480v Three phase Power, permanent or adequate lighting, adequate ventilation, storage areas for shipped materials, a job site dumpster for non-hazardous materials and Ryerson Concrete with MSDS sheets if we will be working in chemical, acids or solvent areas. 2. Have the area(s) cleared of all non-permanent obstructions (i.e., toolboxes, racks, equipment, etc.). Also, have the area(s) broom swept and dry prior to our arrival and make the work area(s) accessible 24 hours per day / 7 days per week, if necessary, in order to complete the project in the time frame required. 3. Post notice to your employees to stay clear of the specified work area(s) during the application process and cure cycle; or provide your employees with proper safety equipment (respirators, glasses, etc.) if they need to be in the specified work area(s).
9. Unforeseen circumstances to be negotiated with owner, architect, general contractor, etc. at time of discovery.

We hereby propose to furnish labor & material - in complete accordance with above specifications, for the sum of:

Base Bid Amount: Thirty five thousand one DOLLARS and no/100 --- **\$35,001.00**

Valid: This proposal may be withdrawn by Ryerson Concrete LLC if not accepted within 30 days from the date above.

Terms: Deposit of 30% is due prior to commencement of work. Progress draws will be invoiced every 30 days or as work progresses. Invoices to be paid net 15 days.

Note: All material is guaranteed to be as specified. All work to be completed in a workmanlike manner according to standard practices. Any alteration or deviation from above specifications involving extra costs will be executed only upon written orders, and will become an extra charge over and above the estimate. All agreements contingent upon strikes, accidents or delays beyond our control. Owner to carry fire, tornado and other necessary insurances. Our workers are fully covered by Workmen's Compensation Insurance.

**Authorized
Signature**

Kenny Ryerson
Ryerson Concrete LLC

Accept: The above prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined above.

Signature

Date of Acceptance

Signature