

Dawn Duranleau

From: Justin Barrett <justin@xbidcsi.com>
Sent: Monday, May 18, 2026 10:56 AM
To: Dawn Duranleau
Subject: Re: Floor Finishes - Bid Follow Request (NCSD Tonopah HS Field)

Hi Dawn,

Yes the Schluter strip is included. We do not install rubber base.

Justin Barrett
702.335.9538
XbidCSI LLC



All hard work brings a profit; but mere talk leads only to poverty.

Proverbs 14:23

From: Dawn Duranleau <dawnduranleau@coreconstruction.com>
Sent: Monday, May 18, 2026 7:48:29 AM
To: Justin Barrett <justin@xbidcsi.com>
Subject: Floor Finishes - Bid Follow Request (NCSD Tonopah HS Field)

Hi Justin,

Can you please confirm / provide Additive Costs for the following items (breakout as indicated):

- **Concrete Finishing**
 1. What product did you quote?
 2. ADD (200 LF) 4" rubber wall base (supply & install)

PART 2 - PRODUCTS

2.01 RESILIENT BASE (RB)

- A. Thermoset Rubber Base:
 - 1. Basis of Design: Roppe Corporation; Pinnacle Rubber Base.
 - 2. Other Manufacturers: Subject to compliance with requirements, provide products of the following:
 - a. Burke Mercer Flooring Products.
 - b. Flexco, Inc.
 - c. Johnsonite.
 - 3. Resilient Base Standard: ASTM F1861, Type TS (rubber, vulcanized thermoset), (solid, homogeneous).
 - 4. Style and Location:
 - a. Style A, Straight: Provide in areas with carpet.
 - b. Style B, Cove: Provide in areas with resilient floor coverings.
 - 5. Minimum Thickness: 0.125 inch (3.18 mm).
 - 6. Height: 4 inches (101.6 mm).
 - 7. Lengths: Coils in manufacturer's standard length.
 - 8. Outside Corners: Preformed.
 - 9. Inside Corners: Job formed.
 - 10. Surface: Smooth
 - 11. Finish: Matte.
 - 12. FloorScore Certified.

2.02 INSTALLATION MATERIALS

- A. Trowelable Leveling and Patching Compounds: Latex-modified, portland cement base blended hydraulic-cement-based formulation provided or approved by manufacturer for applications indicated.
- B. Adhesives: Water-resistant type recommended by manufacturer to suit resilient product substrate conditions indicated.
 - 1. Adhesives shall have a VOC content of 50 g/L or less.
- C. Metal Edge Strips: Extruded aluminum with mill finish of width shown, of height required to protect exposed edges of tiles, and in maximum available lengths to minimize running

- **Fluid-Applied Flooring**

- 1. ADD Schluter strip along top of coved base

Also, please confirm (or provide revised pricing for) current Nye County prevailing wage rates.

Response is respectfully requested by: **05/22/2026**.

Please let me know if you have any questions.

Thank you!

Dawn Duranleau, AIA, CCM, LEED GA

Preconstruction Manager

CORE Construction | West

C: 702-467-0560 | W: coreconstruction.com

From: Justin Barrett (XbidCSI LLC) <team@buildingconnected.com>

Sent: Tuesday, May 12, 2026 6:47 AM

To: Dawn Duranleau <dawnduranleau@coreconstruction.com>
Subject: Proposal Submitted - NCSD - Tonopah High School Sports Co...



Bid submitted from **Justin Barrett** of **XbidCSI LLC** for

NCSD - Tonopah High School Sports Complex: Concrete Finishing

Bid Value: \$10,397

[View the entire bid](#)

Attachments

[Core Constuction - NCSD TONOPAH HS SPORTS COMPLEX ESTM 26208A01 B01 5.12.26 NRC JTB.pdf](#)
[NRC TAKE OFF NCSD - TONOPAH HIGH SCHOOL Sports Complex 5.8.26 JTB.pdf](#)

Vendor Details



Justin Barrett

Owner • +1 702-335-9538 • justin@xbidcsi.com



XbidCSI LLC

9355 Mohawk Street, Las Vegas, NV 89139, United States of America

www.buildingconnected.com [Click here for help](#)

© Copyright 2026 BuildingConnected.com. All Rights Reserved.

925 Mission St, San Francisco, CA 94103