

For Work At

Tonopah High School
1 Ray Tennant Way
Tonopah NV 89049
United States

Billing Address

Dawn Duranleau, PreConstruction Mgr /
Accounts Payable
CORE Construction & Development, Inc.
7150 Cascade Valley Ct
Las Vegas NV 89128-0455
United States

Account Executive

005618 Karen M Munson
YESCO - Reno
800 B Bennie Lane
Reno NV 89512
United States

Date	Project Number	Project Description	Pricing Valid Until	Deposit
05/12/2026	PRY-66188	Tonopah High School Sports Complex	06/11/2026	

Item	Amount
Scope #072 Building Signage YESCO to provide all labor, material, equipment and supervision to supply and install all building signage (interior and exterior) as depicted in drawings G0-11 an A5-10. Includes 9ea Room/Door Signs, 2ea Elec. Room Signs, and 6ea Restroom Signs. Exterior building signage 24" flat cut out painted aluminum letters flush mounted to the concessions building with studs. Copy to read TONOPAH HIGH SCHOOL HOME OF THE MUCKERS. The mascot to be painted by others and is not included in this scope Includes (1) mobilization	
Nevada - Sign Sales Complete scope	\$18,200.00
Scope #078 Flagpole YESCO to provide all labor, material, equipment and supervision to supply and install (1) 30' tall flag pole and (1) 4'x6' US Flag	Price updated to 3 poles = \$24,530
Nevada - Sign Sales Supply flagpole and set in sleeve. GC to dig the hole and set the YESCO supplied sleeve.	-Karen Munson, 05/29/26 \$6,556.00
Nevada - Sign Sales Mobilization	\$2,298.00
Nevada - Sign Sales Add alternate YESCO to dig the hole and set the sleeve	\$1,140.00
Scope #089 Scoreboards YESCO to provide all labor, material, equipment and supervision for the complete scope of work per plans and specifications. EXCLUSION Electrical must be brought within 10' of the scoreboard for	
Nevada - Sign Sales Supply and install (1) Daktronics FB-2021 Football Scoreboard complete with all steel support structural components. Prime and paint structural steel Complete final electrical connection and commissioning of the scoreboard. Provide Nevada Engineering and permits.	\$67,030.00
Nevada - Sign Sales Mobilization	\$3,103.00

Item	Amount
Nevada - Sign Sales Add alternate Supply and install footings included excavation, backfill, compacted subbase, concrete, reinforcing, sleeves, anchors, layout and clean-up. Includes all equipment including concrete pumper truck and auger.	\$29,350.00
Clauses All pricing is based on supplier pricing as of the date of this proposal. All pricing is subject to change due to increases in supplier pricing, changes to tax and tariff rates, and other causes beyond YESCO's reasonable control. Pricing shown will need to be updated after 10 days due to fluctuating materials pricing. Addendum 1 and 2 are acknowledged Southern Rural Nevada Prevailing Wage is acknowledged Nye County Sales Tax included Unforeseen Site Conditions. In the event YESCO encounters unforeseen conditions relating to the intended place of installation (for example, (i) underground conditions such as caliche, hardpan, rock, pipelines, unusual soil conditions, sprinkler systems, and underground utilities; and (ii) in-wall conditions such as reinforced concrete, false walls, firewalls, fire sprinkler lines, electrical wires or conduit, and EIFS) any additional work necessary to address such conditions is excluded from YESCO's scope and YESCO and Customer agrees to pay YESCO to perform the additional work relating to such conditions on a time and material basis at YESCO's standard time and material rates. Customer waives and releases YESCO from any damage or cost arising from damage from unforeseen underground or in-wall conditions unless YESCO is notified in writing of such conditions in advance. Right to Review. In submitting this bid, YESCO reserves the right to review and negotiate any terms and conditions contained in any agreement it may be required to enter into, including general conditions and special conditions, as well as any documents incorporated by reference, upon the acceptance of such bid.	
Exclusions Site Electrical & Low Voltage Systems. Electrical requirements for the scoreboard to be brought within 10' for YESCO to make final electrical connections.	
	Subtotal \$127,677.00
	Tax Total (%) \$0.00
	Total \$127,677.00

This Proposal is subject to acceptance of YESCO's Standard Terms and Conditions, available at www.yesco.com/terms/standardtermsandconditions.pdf. The proposed financing terms are only estimates. Final terms are subject to due diligence and formal credit approval by YESCO Financial Solutions.