



**2667 W. Cheyenne Ave
N. Las Vegas, NV 89032
702-438-7426**

To:	CORE Construction Services of Nevada	Contact:	
Address:	7150 Cascade Valley Ct Las Vegas, NV 89128	Phone:	(702) 794-0550
Project Name:	NCS D Tonopah HS Sports Comple (G)	Fax:	
Project Location:	1 Ray Tennant Wy, Tonopah, NV	Bid Number:	
Addendum #:	3	Bid Date:	5/12/2026

Item #	Item Description	Estimated Quantity	Unit	Total Price
1	Mobilize	2.00	EACH	\$17,883.14
2	Demolish Sod, Turf, Light Pole Bases, Fence, Buildings, Track, Trees & Curbs.	1.00	LS	\$683,842.12
3	Overexcavate For Proposed Building Pad.	1.00	LS	\$11,351.06
4	Mass Grade Site & Export Approx 18,500 Cy To Offsite Location.	1.00	LS	\$947,913.90
5	Cut Subgrade And Provide Type II For Mow Curb.	1,300.00	LF	\$28,262.00
5	Provide And Place 2" Of Asphalt Over 4" Of Aggregate For Access Road.	29,000.00	SF	\$194,300.00
6	Provide And Place 4" Asphalt Over 4" Of Type II For Running Track And Field Event Areas. (1 Mob For Paving)	69,100.00	SF	\$620,518.00
7	Provide And Place Rock For Laydown Yard.	10,000.00	SF	\$23,000.00
8	Provide SWPP Plan And Controls	1.00	LS	\$25,120.78
9	Caliche Allowance For This Scope Of Work.	480.00	CY	\$27,316.80
10	Provide And Place 6" Of Type II For Sidewalks And Building Pad.	1,012.00	TON	\$78,136.52
11	Provide And Place 4" Of Drain Rock Under Turf Area	74,220.00	SF	\$106,876.80
Total Price for above Items:				\$2,764,521.12

Alternates

Alt 8.01	Discount If Awarded Building Wrecking	1.00	EACH	\$6,000.00
Alt 8.02	Caliche Unit Rate. Remove And Replace With Engineered Fill	1.00	CY	\$46.00
Alt 8.03	Add For Demolition At Elementary School Campus. Demolish Existing Buildings And Canopy. Leave Concrete Building Pads And Wall. Includes Dump Fees And Transportation Costs To The Beaty Landfill. Provide Dust Palliative To Disturbed Areas. Asbestos Abatement	1.00	LS	\$1,498,400.00
Alt 8.04	Provide And Place 2" Of Sand And Geo-liner Under Turf Area	74,220.00	SF	\$156,604.20
Total Price for above Alternates Items:				\$1,661,050.20

Total Bid Price: \$4,425,571.32

Notes:

- Exclusions;
Clean up/ haul off behind other contractors
Hard Rock removal or disposal
Placement of Concrete / Slurry.
Permits, drawings, engineering, testing or survey
Traffic Control. Cost of water, SWPP
Excavating / backfill of footings. Erosion control maintenance
Striping, signage, bumper blocks or speed bumps.
Soil sterilant, termite control, weed killer, herbicides.
Supply or placing topsoil, dewatering
Sand under Turf
Sports Pit Material. Javlin Runway Mix
Walls
Dust Palliative

Bond Rate is 2%

Asphalt pricing and Utility Material pricing shall be adjusted at time of placement. Asphalt Pricing shall be reviewed from Bid Date to Pave Date per
NDOT website for POTEN, <https://www.dot.nv.gov/home/> . Utility Material pricing will be adjusted by review of proposals from supplier from Bid
Date to Purchase Date.

NVCL 29174A
Bid Limit 4.5Mil

ACCEPTED:

The above prices, specifications and conditions are satisfactory and
are hereby accepted.

Buyer: _____

Signature: _____

Date of Acceptance: _____

CONFIRMED:

NDX, LLC

Authorized Signature: _____

Estimator: Bianca Soriano Ozuna
702-438-7426 bsoriano@ndxllc.com